

Name of Work: Design, Supply, Installation, Testing & Commissioning in position with all necessary fittings & Accessories, 10 Nos. Passenger lifts (1000Kg) Lifts in Federal Govt. Employees Housing Foundation's Apartment at Sector 24-B, KDA Sch-33 (Corridor), Gulzar-e-Hijri, Karachi


BILL OF QUANTITIES

S	SUB HEAD	Non-Schedule Items			
		QUANTITY	UNIT	RATE	AMOUNT
10	Design, Supply, installation, testing and commissioning putting into operation and final testing of passengers / bed elevators lift of capacity 1000KG with all accessories and control equipment for a total rise of 33 meters with 10 landings (basement, ground to 8th floor) and 10 opening at the rated speed 1.6 meter per second and with power operated doors complete as per the detailed specifications enclosed at Schedule A with motor drive under VVVF control system with or without attendant operation. Brands: US / Western European / Japanese / Turkish / Korean	6	Each		
11	Design, Supply, installation, testing and commissioning putting into operation and final testing of passengers elevator lift of capacity 1000KG with all accessories and control equipment for a total rise of 30 meters with 9 landings (basement, ground to 7th floor) and 9 opening at the rated speed 1.6 meter per second and with power operated doors complete as per the detailed specifications enclosed at (Schedule-A) with motor drive under VVVF control system (with or without attendant) operation. Brands: US / Western European / Japanese / Turkish / Korean	4	Each		
12	Supply at site, fabrication, installation, commissioning and testing of the Power Distribution Boards (PDBs), Protection Classification not less than IP-44, Sheet metal clad 16 SWG for frame and 14 SWG for doors. Totally enclosed wall mounted/ Recessed in wall indoor type with front access and hinged door. including all auxiliaries and interlocking, internal wiring, designation labels on and MCCB's and MCBs. Earthing bar shall be suitable for system Voltage 415 V, 50 Hz, 3 Phase and neutral bus bars of hard drawn bare copper conductor, 99.9% electrolytic copper, Switch Board duly painted with electro static Powder coating of approved colour. Complete in all respects.(Make	4	Each		

6x1000kg
10 stops

4x1000kg
9 stops

Detail provide a under financial bid




Name of Work: Design, Supply, Installation, Testing & Commissioning in position with all necessary fittings & Accessories, 10 Nos. Passenger lifts (1000Kg) Lifts in Federal Govt. Employees Housing Foundation's Apartment at Sector 24-B, KDA Sch-33 (Corridor), Gulzar-e-Hijri, Karachi

BILL OF QUANTITIES

S	SUB HEAD	Non-Schedule Items			
		QUANTITY	UNIT	RATE	AMOUNT
	DB-Lift INCOMING: 01- 40 Amps. T.P. MCCB 3- Phase Indication lamp 1- Ampere Meter 1- Volt Meter 1- Neutral bar 1- Earth bar OUTGOING: 01- 40 Amps. T.P. MCCB 01- 20 Amps. S.P. MCCB 01- 10 Amps. S.P. MCCB	10	Each		
13	Chemically Enhanced Earth using 38 mm dia copper pipe filled with soil conditioning material including 6" dia, 6' deep boring and back filled chemical to enhance conductivity. Complete with termination clamps, 12" dia heavy duty tin plated C.I round cover complete in all respect as required.	10	Each		
14	LED Wall mounted light 1x12 Watt IP-65 (Make Phillips, Lumens, Pierlite or as approved by Engineer incharge).	20	Each		
15	LED Wall mounted light 1x12 Watt IP-65 with protection cover (Make Phillips, Lumens, Pierlite or as approved by Engineer incharge).	50	Each		
TOTAL COST OF WORK NON- SCHEDULE ITEMS				Rs=	

Detail Provided Under financial bid



NOTE:

- 1 The rates quoted shall be inclusive of all taxes and duties (sales tax, service tax, work contract tax, excise duty, import duties and GST etc. as applicable and changes for packing, forwarding and delivery at site)
- 2 The Tenderer shall be conversant with the site conditions before quoting the rate. Site is open to visit with complete guidance from the employer.
- 3 The rates quoted shall include license fee for certification of lift inspector, state government for one year along with commissioning of lift.
- 4 The rates quoted shall be inclusive of minor building works, scaffolding modifying / erection equipment, lifter and crane work etc. and complete the work including machine room and other required accessories as directed by the Employer / Consultant.
- 5 Period for completion of works is 180 days from the date of LOA.
- 6 The Contractor shall arrange water, power etc. at site himself.
- 7 Only the verifiable authorize dealers of brands can participate in bids, Joint Venture / sublet of work is not permissible
- 8 Rates of above mentioned items No. 1, & 2 shall be inclusive of all materials cost as under:-
 - Traction drive with motor suitable for 380 V, 3-Phase 50Hz.
 - Central panel based on control system to achieve variable voltage variable frequency drive system (V.V.V.F)
9. All safety devices and control options. i.e. automatic door, open close time adjustment, Intercom between car and machine room and reception, E.L.D (emergency landing device), Phase Protection devices, over & low voltage protection devices, over current protection device, limit switch, safety edge, emergency car light, alarm buzzer, overload features, ventilation fan, emergency exit, emergency call button, light & fan buttons, inspection / maintenance, lift movement arrows, doors buttons of opening and close, emergency manual drive, gong (chime), door interlock switch, fire emergency service, 50% energy saving system (IGBT), automatic bypass (in case of car is full), pit stop switch, door motor protection timer, voice synthesizer, back ground music, hall button lock protection timer, attendant switch, photo cell.
10. Lift car dimension must be adjusted as per site. Door opening 900mm, Door size 900mm x 2100 mm with automatic central opening. Door jambs wide tapered only ground floor plain stainless steel (1.5mm thickness 304 grade)
11. Door sill extruded hard aluminum Walls high-grade stainless steel plain (1.5 mm thickness 304 grade) Car door hairline plane stainless steel (1.5 mm thickness 304 grade) Entrance column plain finished stainless steel (1.5 mm thickness 304 grade)
Granite flooring of approved design.
Ceiling of approved design.
Operating panels steel, finish micro push button type.
Landing doors opening 900 mm stainless steel (1.5 mm thickness 304 grade) plain.
Transit panel only Ground floors plain finished stainless steel.
Car position indicator dot matrix type.
Eclectic Control Panel including all switch gear to match with elevator control panels including the protection system for the following:
Phase reversal
Phase unbalancing Surge
Protection Device
Over voltage.
Pit Depth = 1500 mm



DETAILS OF RCC ITEMS

- a) Making hole as per specification in the floor of machine room for ropes / belt duly making good including cutting and filling of lift well door switch board & call bell board including required scaffolding.

NOTES:

- 1 The technical data explained for the above lifts is only to inform the minimum requirements and the detail design of the manufacturer alongwith the specifications must be submitted by each bidder with country of origin of manufacturing.
- 2 Pre-Shipment inspection at manufacturer factory by the Consultant / Owners Engineers following items should be available for inspection at the time of visit.
 - a) Control Panel
 - b) Motor
 - c) Door Drive
- 3 The guarantee period shall be 18 (eighteen months) after final commissioning and testing. During the last month of the guarantee period, the Contractor shall demonstrate to the Consultant Engineer that all equipment and accessories are operating to the required specifications. In case if equipment remains out of order for more than 10 days or more guarantee / maintenance period will be extended accordingly.

